

Commissioning GFCH-2-G

Part number: 8044343

FESTO



 [General operating condition](#)

Data sheet

| Feature | Value |
|-----------------------|--|
| Design | Twin-axis system with safety module CAMC-G-S3 |
| Scope of services | Activation of the axes in test mode Data backup and documentation Instruction of machine operators, e.g. in error diagnostics and eliminating errors or in changing the position values Configuration and parameterisation of the axes Optimisation of control parameters and homing Checking of wiring, connections, travel paths and energy chains |
| Work involved on site | 6.5 working hours |
| Customer requirements | Use of Festo components CMMP-OS-...-M3 + CAMC-G-S3 Access to the machine or system Wiring of the CAMC completed and checked according to DIN EN 60204 1x "Safety requirements" appendix filled out in full per controller Mechanical, pneumatic and electrical work is completed Qualified personnel responsible for the machine must be present on the agreed date |
| Provision of services | 8-10 days subject to agreement |